



## Bid Notice Abstract

### Request for Quotation (RFQ)

**Reference Number** 7870825  
**Procuring Entity** NATIONAL WAGES AND PRODUCTIVITY COMMISSION  
**Title** Procurement of Services for the Renovation of NWPC Office Space  
**Area of Delivery** Metro Manila

<b>Solicitation Number:</b>	SVP-2021-07-034	<b>Status</b>	Active
<b>Trade Agreement:</b>	Implementing Rules and Regulations	<b>Associated Components</b>	1
<b>Procurement Mode:</b>	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	<b>Bid Supplements</b>	0
<b>Classification:</b>	Goods	<b>Document Request List</b>	0
<b>Category:</b>	Construction Projects	<b>Date Published</b>	27/07/2021
<b>Approved Budget for the Contract:</b>	PHP 800,000.00	<b>Last Updated / Time</b>	27/07/2021 00:00 AM
<b>Delivery Period:</b>		<b>Closing Date / Time</b>	05/08/2021 12:00 PM
<b>Client Agency:</b>			
<b>Contact Person:</b>	BAC Secretariat Admin Division 2/F DY International Bldg., San Marcelino St. cor. Gen. Malvar Sts., Malate Manila Metro Manila Philippines 1004 63-2-85275171 63-2-5275522 bac_sec.nwpc@yahoo.com		

#### Description

Total Approved Budget: Php 800,000.00

One (1) lot Renovation of NWPC Office Space at 2nd and 3rd floors, DY International Building Corp.  
(Labor and Materials Costs)

#### A. General Requirements

1. Mobilization/Demobilization
2. Tools & Equipment
3. Safety & Health Requirements
4. Bonds & Insurances
  - a. CARI

#### B. 2nd Floor

##### PANTRY, EQUIPMENT & STORAGE

1. Walls
  - a. Installation of Drywall using metal framing & 12mm thk Gypsum Board
  - b. 1.5mm x 100mm Vinyl Baseboard
2. Door
  - a. 900 x 2100 Solid Core Door, including Locksets & Hinges
3. Painting Works
  - a. Drywall

- 4. Joineries
  - a. Supply of Pantry Ledge in Laminate Finish
  - b. Pantry Base & Drawer Cabinet in Laminate Finish
- C. 3rd Floor  
INNOVATION, EA ROOM & RECORDS AREA
  - 1. Walls
    - a. Installation of Drywall using metal framing & 12mm thk Gypsum Board
    - b. 1.5mm x 100mm Vinyl Baseboard
  - 2. Door
    - a. 900 x 2100 Solid Core Door, including locksets & hinges
  - 3. Painting Works
    - a. Drywall
- D. COA Storage and Pantry
  - 1. Walls
    - a. Chipping of walls for new Door
    - b. Dry wall using metal stud, 12mm thk Gypsum Board
    - c. 1.5mm x 100mm Vinyl Baeboard
  - 2. Door
    - Installation of New Door 900 x 2100- Solid Core, locksets included
  - 3. Painting Works
    - a. Drywall
  - 4. Joineries
    - a. Pantry Base Drawer Cabinet in Laminate Finish
    - b. Supply of Pantry Ledge in Laminate Finish
- E. Lactation Room
  - 1. Walls
    - a. Chipping of existing wall tiles
    - b. Plastering of walls
  - 2. Painting Works
    - a. Wall
  - 3. Joineries
    - a. Base Cabinet in Laminated Finish including Counter top
    - b. Vanity Counter for Wash Basin
  - 4. Fixtures
    - a. Countertop Wash Basin including Faucet

## OTHERS:

- 1. Hauling & Disposal of Debris
- 2. Miscellaneous Expenses (Transportation, Communications)
- 3. Contingencies

NOTE: FULL PAYMENT SHALL BE THRU BANK TRANSACTION. PREFERABLY WITH LANDBANK ACCOUNT, OTHERWISE BANK CHARGE SHALL BE FOR THE ACCOUNT OF THE WINNING BIDDER

**Created by** BAC Secretariat

**Date Created** 26/07/2021

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.